

Big Dipper[®] AST Central Automatic Grease Removal Systems

W-750-AST Specifications

PRODUCT FEATURES


- Fully automatic self cleaning cycle. Actively removes collected grease, oils, & solids from tank without any operator assistance. Comes complete with Digital Control and Grease Collector.
- Constructed of corrosion resistant materials suitable for installation in virtually any location. Attractive sanitary Stainless Steel exterior.
- · Integrated Motor/Grease Outlet/Heater/Lid enables a fast, do-it-yourself unit operation reversal.
- · Compact footprint.
- Two (2) No-Hub Connectors provided.

SPECIFICATIONS

Construction:	Exterior: 304 Stainless Steel, Bright Finish Interior: Rotationally Molded Polyethylene
Electrical:	115 VAC, 50/60 Hz, 1400 Watts (12.2 Amps)*
Electrical Cord Length:	8 feet
Flow Rating:	75 GPM (4.73 l/s)
No. of Skimming Wheels:	1
Skimming Rate:	9 Pounds (4.08 Kg) Per Hour
Grease Retention Capacity:	211.11 Pounds (95.8 Kg)
Sepration Efficiency:	_93.8%
Inlet/Outlet:	4" (100 mm)

*For Additional Electrical Configurations, see Electrical Variations section on page 2.

SIDE VIEW




TOP VIEW

46.00 in [1168 ₫ 35.00 in [888.9 mm] CLEARANCE FROM BOTTOM OF TANK REQUIRED FOR REMOVAL OF BASKET STRAINERS 17.85 ii [453.4 m] OUTLET INLE Ø4.50 in ä INLET 25.79[']in [655.2 mm] OUTLET 21.77[']in [553.0 mm] GC-10 GREASE COLLECTOR 7.4 QUART [7 L] CAPACITY 16 59 [421.3 mm] -2.01 in [51.1 mm] 42.23 in [1072.6 mm] ES CE Conforms to ASME Standard ASME A112.14.3 and A112.14.4 ©2020 Thermaco, Inc. • All rights reserved • Patented/Patents Pending • Speci ications subject to change without notice Thermaco, Inc. • PO Box 2548 • Asheboro, NC 27204-2548 • (336) 629-4651 • www.big-dipper.com 5/20 1



Big Dipper[®] AST Central Automatic Grease Removal Systems

W-750-AST Specifications



INSTALLATION NOTES

1. READ instruction manual included with system before installing/operating.

2. Install unit allowing for the minimum clearances shown. Make sure there is sufficient space above Internal Filter access to remove the filter [minimum of 13.23" (336mm)]

3. Make piping connections with rubber "No Hub" connectors.

4. Keep outlet piping as straight as possible. Use only "sweep" connections.

5. Install vent on outlet piping.

6. Fill the tank with water before energizing the power to the motor and heater.

Do not install "P" Trap on outlet connection of tank (unit already has internal gas trap).
Do not reduce pipe size on outlet piping

9. Do not pressure test unit.

Equipment must be installed in compliance with all applicable laws, regulations and codes, including plumbing codes. Installation should be performed by a qualified plumbing contractor.

2

JOB SPECIFICATION

Grease and oils separator(s) shall be Thermaco Big Dipper automatic grease/oil recovery system(s) as manufactured by Thermaco, Inc., Asheboro, North Carolina as noted on plans.

AUTOMATIC GREASE REMOVAL DEVICE SPECIFICATIONS

Furnish and install _____ Thermaco Big Dipper Model No. W-750-AST, bright finish type 304 stainless steel exterior, rotationally molded polyethylene interior automatic self-cleaning grease and oil recovery separator(s) for floor mounted or partially recessed installation, rated to ASME A112.14.3 and PDI-G 101 standards at 75 gallons per minute (4.73 liters per second) peak flow with 211.11 Pounds (95.8 Kg) of grease capacity and including as an integral part of the unit, 4" (100 mm) inlet/outlet, 1 rotating gear hydrophobic wheel assembly for automatic grease/oil removal, an integral flow control device, self-regulating enclosed electric immersion heater, a vessel vent, an integral gas trap, a digital control for programmable operation, a field reversible motor location, a field reversible grease/oil sump outlet, quick release stainless steel lid clamps, a gasketted and fully removable 304 stainless steel lid, a lift-out filter basket access, a centrifugal transfer pump controlled by repeat cycle timer, and a separate grease and oils collection container. Electric assembly shall be tested to comply with pertinent sections of the Standards for Safety ANSI/UL 73 and/ or ANSI/UL 1004. Electric motor equipped with overload protection. Two (2) no-hub connectors for plumbing connection provided.

ELECTRICAL VARIATIONS

- U W-750-AST: 115V 50/60Hz, 1400 Watts (12.2 Amps)
- U W-750-AST-E: 230V 50/60Hz, 1400 Watts (6.1 Amps)

SUBMITTAL OPTIONS

- □ FS-1 Point Source Flat Strainer (3.4 Gallons of additional solids storage capacity)
- □ ILS-1 In-Line Strainer (4 Gallons of additional solids storage capacity)
- □ SFK-3 Support Frame Kit, stainless steel construction, for use with 55 Gallon Grease Barrel (DRUM-55)
- DRUM-55 Grease Barrel with 55 gallon capacity, requiress use of SH-3 on each Electrical Assembly
- □ SH-3-KIT Sump Hose and clamp for grease trough connection to DRUM-55
- □ AP-6000-1-DR Alarm Probe for 55 Gallon Grease Barrel (DRUM-55) to notify when full of grease
- AP-6000-1-DRDC Alarm Probe for 55 Gallon Grease Barrel (DRUM-55) dry contact for remote warning light notification when full
- AP-6000-1-TK Alarm Probe for Big Dipper unit
- AP-6000-1-TKDC Alarm Probe for Big Dipper unit, dry contact for remote warning light notification

©2020 Thermaco, Inc. • All rights reserved • Patented/Patents Pending • Speci ications subject to change without notice Thermaco, Inc. • PO Box 2548 • Asheboro, NC 27204-2548 • (336) 629-4651 • www.big-dipper.com